

# BULLETIN # 0 6

**DATE:** April 7, 2025

**TO:** Piazza Inc.  
Attn: Gus Carvajal

**CC:** Jordan Medina, Hill Intl.,

**FROM:** Brian Dunn, AIA  
KG+D Architects, PC

**PROJECT:** Harrison Recreation & Community Center – PHASE 2  
Harrison, NY

**RE:** Revised Door Schedule



## Message:

Please see the attached Door Schedule revising Door 203B to a Wood Door in a Hollow Metal Frame. The door pair elevation FLNG remains unchanged.

Cc: File

Encl: Revised Door Schedule

### **KG+D Architects, PC**

285 Main Street, Mount Kisco, New York 10549  
914.666.5900 kgdarchitects.com

**HARRISON RECREATION & COMMUNITY CENTER**

New Construction - Phase 2  
Town / Village of Harrison  
270 Harrison Avenue  
Harrison, NY 10528



**KG+D ARCHITECTS, PC**  
285 MAIN STREET • MOUNT KISCO, NEW YORK 10549  
P:914.666.5900 KGDARCHITECTS.COM

**CONSTRUCTION DOCUMENTS**

**GENERAL NOTES**

- GLAZING IN FIRE RATED DOORS SHALL BE FIRE RATED GLAZING TO MEET THE FIRE RATING SCHEDULED, UNLESS NOTED OTHERWISE.
- G.C. SHALL VERIFY SIZE OF REPLACEMENT DOORS & FRAMES IN THE EXISTING BUILDING BEFORE ORDERING.
- SEE SPEC. SECTION 08 71 00 FOR DOOR HARDWARE SETS, HARDWARE NOTES, COMPONENTS & OTHER INFORMATION.
- EXTERIOR DOOR PAIRS SHALL HAVE AN ALUMINUM KEYPED REMOVABLE MULLION WITH RIM CYLINDER EXIT DEVICE W/KEYED CYLINDER DOGGING.
- INTERIOR DOOR PAIRS SHALL HAVE AN HOLLOW METAL KEYPED REMOVABLE MULLION WITH RIM CYLINDER EXIT DEVICE W/KEYED CYLINDER DOGGING, EXCEPTION IS CROSS-CORRIDOR DOOR PAIRS & DOORS INTO STAIRS.
- FRP DOORS SHALL HAVE SUITABLE BLOCKING FOR LEVER OR ARCHITECTURAL PULLS. RECESSED PULL NOT ACCEPTABLE.
- FACE OF ADJACENT WALL TO EDGE OF DOOR FRAME IS 4" (TYPICAL) U.N.O. SEE DETAILS A & B ON A9.2.

NOTE: ALL LEGAL DESIGN, ARRANGEMENTS AND PLANS INDICATED OR REPRESENTED BY THIS DRAWING ARE OWNED BY AND ARE THE PROPERTY OF KG+D ARCHITECTS, PC AND ARE NOT TO BE REPRODUCED OR USED FOR ANY PROJECT, PART OF SUCH LEGAL DESIGN, ARRANGEMENTS OR PLANS SHALL BE USED BY OR FOR OTHERS TO ANY PURPOSE WHATSOEVER WITHOUT THE WRITTEN PERMISSION OF KG+D.

WRITTEN ORDERS ON THIS DRAWING SHALL HAVE PRECEDENCE OVER ALL OTHERS. CONTRACTOR SHALL VERIFY ALL ACTUAL CONDITIONS AND CONDITIONS ON THE JOB AND THE ARCHITECT MUST BE NOTIFIED OF ANY VARIATIONS FROM CONDITIONS AND CONDITIONS SHOWN. DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL, BEFORE PROCEEDING WITH CONSTRUCTION.

ALTERATIONS BY ANY PERSON IN ANY WAY OF ANY VIEW CONTAINED ON THIS DOCUMENT, UNLESS ACTING UNDER THE DIRECTION OF THE LICENSED ARCHITECT, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY OF TITLE 16, SECTION 28-B (a) OF NEW YORK STATE LAW. ALL RIGHTS RESERVED.

Professional Seal



No.	Date	Issue
9	04/07/2025	BULLETIN 7
7	10/09/2024	FOR CONSTRUCTION
7	10/09/2024	CONFORMED SET
4	06/05/2024	ISSUED FOR BID
3	01/16/2024	ISSUED FOR PERMIT
2	06/01/2020	DESIGN DEVELOPMENT
1	03/31/2020	50% DESIGN DEVELOPMENT

Sheet Title

**DOOR SCHEDULE & TYPICAL DOOR DETAILS**

Job No.	2020-1005	Date	-
Scale	AS NOTED	Drawn / Checked	-
Sheet Number	A911		

Mark	Room	# LEAVES	WI	HT	Elev	Door Mat	Door Fin	Fram e Mat	Frame Fin	Frame Type	Fire Label	Saddle	HDWE SET	MH/CR	Comments
PARKING															
B01	PARKING	1	3'-0"	7'-0"	F	FRP	FF	HM	PTD	01M		AL	5.0	CR	
B03	ELEC	1	3'-0"	7'-0"	F	HM	PTD	HM	PTD	01M	45 MIN	AL	28.0		
B04A	STORAGE	2	6'-0"	7'-0"	F	HM	PTD	HM	PTD	02M		AL	27.0		
B04B	STORAGE	1	3'-0"	7'-0"	F	HM	PTD	HM	PTD	01M		AL	26.0		
B05	OFFICE	1	3'-0"	7'-0"	F	FLNG	HM	PTD	HM	PTD	01M		AL	18.0	
B06A	MECH	2	6'-0"	7'-0"	F	HM	PTD	HM	PTD	02M	45 MIN	AL	27.0		
B06B	MECH	2	6'-0"	7'-0"	F	HM	PTD	HM	PTD	02M	45 MIN	AL	27.0		
B07	MECH	2	6'-0"	7'-0"	F	HM	PTD	HM	PTD	02M	45 MIN	AL	27.0		
B08	EMR	2	6'-0"	7'-0"	F	WD	FF	HM	PTD	02M		AL	27.0		
SA0	STAIR A	1	3'-0"	7'-0"	F	FLNG	HM	PTD	HM	PTD	01M	60 MIN	AL	23.0	
SB0	STAIR B	1	3'-0"	7'-0"	F	FLNG	HM	PTD	HM	PTD	01M	60 MIN	AL	22.0	
SD0A	STAIR D	1	3'-0"	7'-0"	F	FLNG	HM	PTD	HM	PTD	01M	60 MIN	AL	23.0	
SD0B	STAIR D	1	3'-0"	7'-0"	F	FLNG	HM	PTD	HM	PTD	01M	60 MIN	AL	23.0	

1st FLOOR	Room	# LEAVES	WI	HT	Elev	Door Mat	Door Fin	Fram e Mat	Frame Fin	Frame Type	Fire Label	Saddle	HDWE SET	MH/CR	Comments	
100A	VESTIBULE	1	3'-0"	8'-0"	WS1	AL	FF	AL	FF	A9		AL	1.0	CR	SECURITY GLAZING @ DOOR & SIDELITES, ADA AUTO OPEN.	
100B	VESTIBULE	2	6'-0"	8'-0"	WS1	AL	FF	AL	FF	A9		AL	2.0		SECURITY GLAZING @ DOOR & SIDELITES.	
100C	VESTIBULE	1	3'-0"	8'-0"	WS1	AL	FF	AL	FF	A9		AL	3.0		SECURITY GLAZING @ DOOR & SIDELITES.	
100D	LOBBY	1	3'-0"	8'-0"	WS1	AL	FF	AL	FF	A8			1.0	CR	SECURITY GLAZING @ DOOR & SIDELITES, ADA AUTO OPEN.	
100E	LOBBY	2	6'-0"	8'-0"	WS1	AL	FF	AL	FF	A8			2.0		SECURITY GLAZING @ DOOR & SIDELITES.	
100F	LOBBY	1	3'-0"	8'-0"	WS1	AL	FF	AL	FF	A8			3.0		SECURITY GLAZING @ DOOR & SIDELITES.	
103	OPEN OFFICE	1	3'-0"	7'-0"	F	WD	FF	HM	PTD	H2			20.0	CR		
103B	CONF	1	3'-0"	7'-0"	F	WD	FF	HM	PTD	H2			18.0			
104	JANITOR	1	3'-0"	7'-0"	F	WD	FF	HM	PTD	01		SL	26.0			
105	TOILET	1	3'-0"	7'-0"	F	WD	FF	HM	PTD	01		SL	29.0			
106A	RECREATION	1	3'-0"	7'-0"	F	WD	FF	HM	PTD	H1			17.0	CR		
106B	RECREATION	1	3'-0"	7'-0"	F	WD	FF	HM	PTD	H1			17.0	CR		
107	COMPUTER	1	3'-0"	7'-0"	F	WD	FF	HM	PTD	H1			20.0	CR		
107A	STORAGE	1	3'-0"	7'-0"	F	HM	PTD	HM	PTD	01M			24.0			
108	ARTS/ CRAFTS	1	3'-0"	7'-0"	F	WD	FF	HM	PTD	H5		SL	20.0	CR		
108A	STORAGE	1	3'-0"	7'-0"	F	HM	PTD	HM	PTD	01			24.0			
109	WOMEN	1	3'-0"	7'-0"	F	WD	FF	HM	PTD	01		SL	30.0			
110	MEN	1	3'-0"	7'-0"	F	WD	FF	HM	PTD	01		SL	30.0			
111	DATA	1	3'-0"	7'-0"	F	HM	PTD	HM	PTD	01			20.0	CR		
112	MEETING	1	3'-0"	7'-0"	F	WD	FF	HM	PTD	H4			18.0			
112A	MECH	1	3'-0"	7'-0"	F	HM	PTD	HM	PTD	01			26.0			
113A	GYM	2	6'-0"	7'-0"	F	FLNG	HM	PTD	HM	PTD	02M		14.0			
113B	GYM	1	3'-0"	7'-0"	F	FLNG	HM	PTD	HM	PTD	01M		15.0			
113C	STORAGE	2	6'-0"	7'-0"	F	HM	PTD	HM	PTD	02M			25.0		UNDERCUT 1"	
113D	CORR	1	3'-0"	7'-0"	F	FLNG	HM	PTD	HM	PTD	01M		21.0			
113E	ELEC	1	3'-0"	7'-0"	F	HM	PTD	HM	PTD	01M	45 MIN		26.0			
113F	STORAGE	2	6'-0"	7'-0"	F	HM	PTD	HM	PTD	02M			25.0		UNDERCUT 1"	
113G	GYM	2	6'-0"	7'-0"	F	FLNG	FRP	FF	AL	FF	02M		7.0			
113H	GYM	2	6'-0"	7'-0"	F	FLNG	FRP	FF	AL	FF	02M		7.0			
113J	STORAGE	2	6'-0"	7'-0"	F	HM	PTD	HM	PTD	02M			25.0		UNDERCUT 1"	
113K	STORAGE	2	6'-0"	7'-0"	F	HM	PTD	HM	PTD	02M			25.0		UNDERCUT 1"	
113L	ELEC	2	6'-0"	7'-0"	F	HM	PTD	HM	PTD	02M	45 MIN		27.0			
113M	GYM	2	6'-0"	7'-0"	F	FLNG	HM	PTD	HM	PTD	02M		14.0			
114A	EAST CORR	1	3'-0"	8'-0"	WS1	AL	FF	AL	FF	H3			10.0	MH		
114B	EAST CORR	1	3'-0"	8'-0"	WS1	AL	FF	AL	FF	H3			10.0	MH		
114C	EAST CORR	1	3'-0"	8'-0"	WS1	AL	FF	AL	FF	H3	60 MIN		9.0	MH		
114D	EAST CORR	1	3'-0"	8'-0"	WS1	AL	FF	AL	FF	H3	60 MIN		9.0	MH		
115	LOCKER CORR	2	6'-0"	8'-0"	WS1	AL	FF	AL	FF	02		AL	1.1	CR	SECURITY GLAZING @ DOOR & SIDELITES.	
118	FAMILY TOILET	1	3'-0"	7'-0"	F	WD	PTD	HM	PTD	01		SL	29.0			
119	JANITOR	1	3'-0"	7'-0"	F	HM	PTD	HM	PTD	01		SL	26.0			
122	MECH	2	6'-0"	7'-0"	F	FRP	FF	AL	FF	02		AL	8.0	CR		
123	FITNESS	2	6'-0"	7'-0"	F	FLNG	WD	FF	HM	PTD	02		16.0			
123A	STORAGE	2	6'-0"	7'-0"	F	HM	PTD	HM	PTD	02			25.0		UNDERCUT 1"	
123B	FITNESS	2	6'-0"	7'-0"	F	FLNG	FRP	FF	AL	FF	02		AL	6.0		
C101	CORR	1	3'-0"	7'-0"	F	FLNG	HM	PTD	HM	PTD	01		21.0			
SA1	STAIR A	1	3'-0"	7'-0"	F	FLNG	WD	FF	HM	PTD	01M		60 MIN		21.0	
SA1A	STAIR A	1	3'-0"	7'-0"	F	FLNG	WD	FF	HM	PTD	01M		45 MIN		5.0	
SB1	STAIR B	1	3'-0"	7'-0"	F	FLNG	WD	FF	HM	PTD	01M		60 MIN		21.0	
SB1	STAIR B	1	3'-0"	7'-0"	F	FLNG	WD	FF	HM	PTD	01M		60 MIN		21.0	

2nd FLOOR	Room	# LEAVES	WI	HT	Elev	Door Mat	Door Fin	Fram e Mat	Frame Fin	Frame Type	Fire Label	Saddle	HDWE SET	MH/CR	Comments
200A	TRACK	1	3'-0"	8'-0"	WS1	AL	FF	AL	FF	A2			12.0		
200B	TRACK	1	3'-0"	8'-0"	WS1	AL	FF	AL	FF	A3			12.0		
202A	MULTI-PURPOSE	1	2'-10"	8'-0"	WS1	AL	FF	AL	FF	04			12.0		
202B	MULTI-PURPOSE	1	3'-0"	8'-0"	WS1	AL	FF	AL	FF	A1			12.0		
203A	MULTI-PURPOSE	1	2'-10"	8'-0"	WS1	AL	FF	AL	FF	04			12.0		
203B	MULTI-PURPOSE	2	6'-0"	7'-0"	F	FLNG	WD	FF	HM	PTD	02		13.0		
203C	MULTI-PURPOSE	1	3'-0"	7'-0"	F	FLNG	WD	FF	HM	PTD	01		26.0		CR
205B	STORAGE	1	3'-0"	7'-0"	F	WD	FF	HM	PTD	01			26.0		
206	PANTRY	1	3'-0"	7'-0"	F	FLNG	WD	FF	HM	PTD	01		19.0		
207	WOMEN	1	3'-0"	7'-0"	F	WD	FF	HM	PTD	01		SL	30.0		
208	MEN	1	3'-0"	7'-0"	F	WD	FF	HM	PTD	01		SL	30.0		
209	ELEC	1	3'-0"	7'-0"	F	WD	FF	HM	PTD	01	45 MIN		26.0		
209A	EMR	2	5'-0"	7'-0"	F	WD	FF	HM	PTD	02			27.0		
210	JANITOR	1	3'-0"	7'-0"	F	WD	FF	HM	PTD	01		SL	26.0		
211	TOILET	1	3'-0"	7'-0"	F	WD	FF	HM	PTD	01		SL	29.0		
212	OPEN OFFICE	1	3'-0"	8'-0"	WS1	AL	FF	AL	FF	A6			11.0		
212A	OFFICE	1	3'-0"	7'-0"	F	WD	FF	HM	PTD	H2			18.0		
212B	CONF	1	3'-0"	7'-0"	F	WD	FF	HM	PTD	H2			18.0		
212C	OFFICE	1	3'-0"	7'-0"	F	WD	FF	HM	PTD	H2			18.0		
C201	TERRACE	1	3'-0"	7'-0"	WS1	AL	FF	AL	FF	A4		AL	4.0		
SA2	STAIR A	1	3'-0"	7'-0"	F	FLNG	WD	FF	HM	PTD	01M		60 MIN		21.0
SB2A	STAIR B	1	3'-0"	7'-0"	F	FLNG	WD	FF	HM	PTD	01M		60 MIN		21.0
SB2B	STAIR B	1	3'-0"	7'-0"	F	FLNG	WD	FF	HM	PTD	01M		60 MIN		21.0

**DOOR GENERAL NOTES**

- GENERAL NOTES:**
- DOORS, FRAMES, SIDELIGHTS, TRANSOMS & ASSOCIATED GLAZING SHALL MEET SCHEDULED FIRE RATINGS.
  - GLAZING IN DOORS, SIDELIGHTS & WITHIN 18" OF GRADE, FLOORS, & STAIR LANDINGS SHALL BE LAMINATED SAFETY GLASS, U.N.O., ALL GLAZING IN AREAS WHERE USE MAY CAUSE PHYSICAL ABUSE, SUCH AS GYMNASIUMS & PLAYROOMS SHALL BE SAFETY GLAZING, SAFETY GLAZING SHALL BE IDENTIFIED & LABELED AS SAFETY GLAZING.
  - CONTRACTOR SHALL VERIFY SIZES OF EXISTING DOORS & FRAMES NOTED FOR REPLACEMENT PRIOR TO ORDERING.
  - SEE DOOR SCHEDULE & SPECIFICATION FOR DOOR HARDWARE SETS, HARDWARE NOTES, COMPONENTS & OTHER INFORMATION.
  - EXTERIOR DOOR SYSTEMS SHALL BE FULLY PERIMETER CAULKED TO ADJACENT FINISHED SURFACES, BOTH INTERIOR & EXTERIOR EXCEPT WHERE SUCH ACTIONS WOULD DISRUPT PROPER DRAINAGE TO THE EXTERIOR.
  - EXTERIOR DOOR PAIRS SHALL HAVE AN ALUMINUM KEYPED REMOVABLE MULLION, PLUG TYPE WIRING HARNESS, RIM CYLINDER EXIT DEVICE WITH KEYED CYLINDER DOGGING. EXCEPTIONS ARE CROSS-CORRIDOR, STAIR & FIREWALL DOORS.
  - INTERIOR DOOR PAIRS SHALL HAVE A HOLLOW METAL KEYPED REMOVABLE MULLION, PLUG TYPE WIRING HARNESS, RIM CYLINDER EXIT DEVICE WITH KEYED CYLINDER DOGGING. EXCEPTIONS ARE CROSS-CORRIDOR, STAIR & FIREWALL DOORS.
  - SEE DOOR SCHEDULE FOR DOOR & FRAME FINISHES.
  - DOORS SHALL HAVE SUITABLE BLOCKING FOR LEVERS OR ARCHITECTURAL PULLS.
  - COORDINATE KEYING WITH OWNER PRIOR TO ORDERING HARDWARE.
  - ALL NEW & REPLACEMENT INTERIOR DOOR FRAMES SHALL BE FULLY WELDED TYPE, KNOCKDOWN (KD) FRAMES SHALL NOT BE USED.
  - VERIFY HOLD-OPENS & STOPS WITH ADJACENT CONDITIONS.
- DOOR SADDLE NOTES:**
- COORDINATE DOOR UNDERCUT WITH SADDLE & OTHER UNDERCUTTING REQUIRED. SEE DOOR SCHEDULE & SADDLE DETAILS ON THIS SHEET.
  - SADDLES SHALL BE FULL WIDTH OF DOOR FRAME.